

DOI: 10.21767/2254-609X.100038

A Mathematical Method for Calculating the Anterior and Superior Axial Coverage Angle of Acetabulum to Femoral 5 Head based on 3D Coordinate System

Zhen-hua Zhang, Ming-xing Wang, Fu-jie Sun, Ke-zheng Hu, Wen-bo Nie, Hong-biao Li and Jie Li

Department of Orthopedics, Huxi Hospital (Shanxian central Hospital), Jining Medical University, China

Corresponding author: Zhen-hua Zhang, Department of Orthopedics, Huxi Hospital (Shanxian central Hospital), Jining Medical University, Shanxian 274300, Shandong, China, Tel: 0530-4558736; Email: zhzhang197422@sina.com

Rec Date: May 5, 2016; **Acc Date:** June 27, 2016; **Pub Date:** July 4, 2016

Copyright: © 2016 Zhang ZH, et al. This is an open-access article distributed under the terms of the Creative Commons Attribution License, which permits unrestricted use, distribution, and reproduction in any medium, provided the original author and source are credited.

Citation: Zhang ZH, Wang MX, Sun FJ, et al. A Mathematical Method for Calculating the Anterior and Superior Axial Coverage Angle of Acetabulum to Femoral Head Based on 3D Coordinate System. J Biomedical Sci. 2016, 5:3.

Abstract

Background: Direct imaging measurement of the anterior and superior axial coverage angle of acetabulum to femoral head is difficult. This study aimed to build the mathematical formulas to calculate them using the available parameters, e.g., acetabular abduction angle.

Results: A 3D coordinate system was established by setting the center of the hip joint rotation basing as coordinate center O. In the drawn diagrams of anterior and superior axial coverage angle of acetabulum to femoral head, femoral neck anteversion was set as a, acetabular abduction angle as b, acetabular anteversion as A, and femoral neck-shaft angle as J. In the absence of the anteversion of acetabular and femoral neck, the superior axis coverage angle of acetabulum to the femoral head equals to $b + 180 - J$. The anterior axial coverage angle of acetabulum to femoral head equals to 90 degrees. In the presence of the acetabular and femoral neck anteversion, the superior axis coverage angle of acetabulum to the femoral head equals to $\arctg \{ \text{tgb} / [\cos \text{acos} (A + a)] \} + 180 - J$; the anterior axis coverage angle of acetabulum to the femoral head equals to $90 - \arctg \{ \text{tg} (A + a) / \cos \{ \arctg \{ \text{tgb} / (\text{cosa} + a) \} - (J - 90) \} \}$. The close relationship between the acetabulum and femoral head spatial orientation angle was observed in the absence of acetabular and femoral neck anteversion. The superior axis coverage angle of acetabulum to the femoral head was positively correlated with acetabular abduction angle and negatively with femoral neck-shaft angle. While the anterior axial coverage angle of acetabulum to femoral head was not dependent on acetabular abduction angle and femoral neck-shaft angle. In the presence of acetabular and femoral neck anteversion, both anterior and superior axial coverage angle of acetabulum to femoral head were relevant to acetabular abduction angle and femoral neck-shaft angle. The superior axial coverage angle of acetabulum to femoral head positively correlated with acetabular abduction angle, negatively with femoral neck-shaft angle, and positively with acetabular and femoral neck anteversion. The anterior axial coverage angle of acetabulum to femoral head was negatively correlated with acetabular abduction angle, positively with femoral neck-shaft angle and negatively with acetabular and femoral neck anteversion.

Conclusions: The formulas were built based on a 3D coordinate system established in the current study. The formula reflects the inner relationship of spatial orientation angle of acetabulum to femoral head, which will offer a simple, novel and efficient mathematical method to calculate the anterior and superior axial coverage angle.

Keywords: Acetabulum; Femoral head; Anteversion; Abduction angle; Neck-shaft angle; Superior axial Coverage angle; Anterior axial coverage angle; Calculation formula

Background

The stabilization of hip joint was maintained by the bony acetabulum covering femoral head, articular cartilage, joint capsule, and surrounding soft tissue. Acetabular and femoral head spatial orientation angles include acetabular abduction angle, anteversion and femoral neck-shaft angle, and anteversion. The exact match of these spatial orientation angles plays a vital role in maintaining the normal range of motion and joint stability. Without this exact match will result in hip dysplasia [1,2], lead to hip instability or femoral acetabular impingement, cause hip wear, followed by hip osteoarthritis [3-9]. The current study on hip phase parameters mainly concentrated on the acetabulum supported femoral head. The femoral head and neck phase parameters were not taken into account, because they did not reflect the intrinsic relationship between acetabular abduction angle and anteversion, and femoral neck-shaft angle and anteversion. This study was designed to establish 3D coordinate systems concerning the anterior and superior axial coverage angle of acetabulum to femoral head, which display the intrinsic relationship of the spatial orientation angles between the acetabulum and femoral head. Eventually, the mathematical formulas were built and the influence factors were evaluated.

Methods

The mathematical calculation of anterior and superior axial coverage angle of acetabulum to femoral head in the absence of acetabulum and femoral neck anteversion.

The 3D coordinate system was established by setting O as the hip rotation center, X axis as the body coronal axis, Y-axis as the body vertical axis, Z-axis as the body sagittal axis (**Figure 1**). In this system, AB served as the femoral shaft axis, DA as femoral head-neck axis, and Y-axis parallel to AB axis. The angle b formed by OC and Y axis was acetabular abduction angle and $\angle OAB$ was the femoral neck-shaft angle indicated by J. $\angle COD$ was formed by segment OD (femoral head-neck axis) and segment OC. Segment OC was formed by the intersection of the plane where Y-axis and femoral head-neck axis lie in and the acetabular exit plane. $\angle COD$ was named as superior axial coverage angle of acetabulum to femoral head. $\angle EOD$ was formed by segment OD (femoral head-neck axis) and segment OE. Segment OE was formed by the intersection of the plane where Z-axis and femoral head-neck axis lie in and the acetabular exit plane. $\angle EOD$ was named as anterior axial coverage angle of acetabulum to femoral head.

Without acetabular and femoral neck anteversion, the plane femoral head-neck axis and Y-axis lie in and the plane femoral head-neck axis and Z-axis lie in were perpendicular to the plane of the acetabular exit. So in this case the superior axial coverage angle of acetabulum to femoral head equals to the abduction angle plus the supplementary angle of femoral neck-shaft angle. It can be expressed as $\angle COD = b + 180 - J$.




Figure 1 The schematic diagram of anterior and superior axial coverage angle of acetabulum to femoral head in the absence of acetabulum and femoral neck anteversion.

The mathematical calculation of superior axial coverage angle of acetabulum to femoral head in the presence of acetabulum and femoral neck anteversion.

The 3D coordinate system was built by setting the hip rotation center as O, X axis as the body coronal axis, Y-axis as the body vertical axis, Z-axis as the body sagittal axis (**Figure 2**). In this system, AB was the femoral shaft axis, DA as femoral head-neck axis and Y-axis parallel to AB axis. $\angle OAB$ was femoral neck-shaft angle indicated by J and the angle b formed by OC and Y axis was acetabular abduction angle. $\angle EOD$ was formed by segment OD (femoral head-neck axis) and segment OE. Segment OE was formed by the intersection of the plane where Y-axis and femoral head-neck axis lie in and the acetabular exit plane. $\angle EOD$ was named as superior axial coverage angle of acetabulum to femoral head.

The plane OC and Z-axis lie in was perpendicular to the plane of acetabular exit and Y-axis was perpendicular to the plane EFG. Based on the 3D-system (**Figure 2**), the superior axial coverage angle of acetabulum to femoral head can be calculated using this equation: $\angle EOD = \angle FOE + 180 - J$. $\angle EFG$ equals to femoral neck anteversion plus acetabular anteversion A. $\angle FOC'$ was acetabular abduction angle indicated by b . It was a projection angle in the coronal plane formed by $\angle FOC$ forward A around the Y axis. So $\angle FOC = \arctg(\text{tg}b/\cos A)$. $\angle FOC$ was a projection angle of $\angle FOE$ in the plane COF formed by $\angle FOE$ forward A+a around the Y axis. So $\angle FOE = \arctg\{\text{tg}b/[\cos A \cos(A+a)]\}$. Therefore, the superior axial coverage angle of acetabulum to femoral head $\angle EOD = \angle FOE + 180 - J = \arctg\{\text{tg}b/[\cos A \cos(A+a)]\} + 180 - J$.




Figure 2 The schematic diagram of superior axial coverage angle of acetabulum to femoral head in the presence of acetabulum and femoral neck anteversion.

The mathematical calculation of anterior axial coverage angle of acetabulum to femoral head in the presence of acetabulum and femoral neck anteversion

As shown in **Figure 3**, the 3D coordinate system was built by setting O as the hip rotation center, X axis as coronal axis of the body, Y-axis as the body vertical axis, Z-axis as the body sagittal axis. In this system, AB was the femoral shaft axis, DA as femoral head-neck axis, and Y-axis parallel to AB axis. $\angle OAB$ was the femoral neck-shaft angle indicated by J and the plane COD was perpendicular to the acetabular exit plane in the absence of acetabular and femoral neck anteversion. $\angle EOD$ was formed by segment OD (femoral head-neck axis) and segment OE. Segment OE was formed by the intersection of the plane where Z-axis and femoral head-neck axis lie in and the acetabular exit plane. $\angle EOD$ was named as anterior axial coverage angle of acetabulum to femoral head. Y-axis was perpendicular to the plane FOG. $\angle HOC'$ was acetabular abduction angle b .

Based on the system, the anterior axial coverage angle of acetabulum to femoral head can be calculated by $\angle GOD = \angle FOD - \angle FOE = 90 - \angle FOE$. $\angle GOF$ equals to femoral neck anteversion plus acetabular anteversion A. $\angle HOC'$ was acetabular abduction angle b , which was a projection angle in the coronal plane formed by $\angle HOC$ forward A+a around the Y axis. So $\angle HOC = \arctg[\text{tg}b / (\cos A + a)]$. $\angle GOF$ was A + a, which was a projection angle in the cross section formed by $\angle FOE$

relationship of spatial angles between the acetabulum and femoral head, which exactly maintain the anterior and superior axial coverage of the acetabulum to the femoral head, maintain hip stability and meet hip normal range of motion. At present, direct imaging measurement of the anterior and superior axial coverage angle of acetabulum to femoral head is difficult. The imaging measurement of the acetabular abduction angle, anteversion, femoral neck anteversion and neck-shaft angle has been established. Consequently, the anterior and superior axial coverage angle of acetabulum to femoral head could be readily calculated using the mathematical formulas built in the current study. For example, based on the normal range of acetabular abduction angle ($45^{\circ} \pm 10^{\circ}$) [12-16], acetabular anteversion ($15^{\circ} \pm 10^{\circ}$) [12-15,17-19], femoral neck-shaft angle (110° - 140°) [20], and the femoral neck anteversion (12° - 15°) [21,22] in the previous studies, the normal ranges of the superior and anterior axial coverage angle of acetabulum to femoral head can be calculated out by the mathematical formulas being 76.32° ~ 134.07° and 41.62° ~ 72.91° , respectively.

Conclusions

In summary, the formula was built based on a 3D coordinate system established in this study. The formula reflects the inner relationship of spatial orientation angle of acetabulum to femoral head, which will offer a simple, novel and efficient mathematical method to calculate the anterior and superior axial coverage angle.

Competing interests

The authors declare that they have no competing interests.

References

1. Crowe JF, Mani VJ, Ranawat CS (1979) Total hip replacement in congenital dislocation and dysplasia of the hip. *J Bone Joint Surg Am* 61: 15-23.
2. Garvin KL, Bowen MK, Salvati EA, Ranawat CS (1991) Long-term results of total hip arthroplasty in congenital dislocation and dysplasia of the hip. A follow-up note. *J Bone Joint Surg Am* 73: 1348-1354.
3. Eijer H, Myers SR, Ganz R (2001) Anterior femoroacetabular impingement after femoral neck fractures. *J Orthop Trauma* 15: 475-481.
4. Goodman DA, Feighan JE, Smith AD, Latimer B, Buly RL (1997) Subclinical slipped capital femoral epiphysis: relationship to osteoarthritis of the hip. *J Bone Joint Surg Am* 79: 1489-1497.
5. Snow SW, Keret D, Scarangella S, Bowen J (1993) Anterior impingement of the femoral head: a late phenomenon of Legg-Calvé-Perthes' disease. *J Pediatr Orthop* 13: 286-289.
6. Myers SR, Eijer H, Ganz R (1999) Anterior femoroacetabular impingement after periacetabular osteotomy. *Clin Orthop Relat Res* 363: 93-99.
7. Reynolds D, Lucas J, Klaue K (1999) Retroversion of the acetabulum: a cause of hip pain. *J Bone Joint Surg Br* 8: 281-288.
8. Ziebarth K, Balakumar J, Domayer S, Kim YJ, Millis MB (2011) Bernese periacetabular osteotomy in males: is there an increased risk of femoroacetabular impingement (FAI) after Bernese periacetabular osteotomy? *J Clin Orthop Relat Res* 469: 447-453.
9. Imai H, Kamada T, Takeba J, Shiraishi Y, Mashima N, et al. (2014) Anterior coverage after eccentric rotational acetabular osteotomy for the treatment of developmental dysplasia of the hip. *J Orthop Sci* 19: 762-769.
10. Anda S, Svenningsen S, Dale LG (1986) The acetabular sector angle of the adult hip determined by computed tomography. *Acta Radiol Diagn (Stockh)* 27: 443-447.
11. Delaunay S, Dussault RG, Kaplan PA (1997) Radiographic measurements of dysplastic adult hips. *Skeletal Radiol* 26: 75-81.
12. Lima DD, Urquhart AG, Buehler KO, Walker RH, Colwell CW (2000) The effect of the orientation of the acetabular and femoral components on the range of motion of the hip at different head neck ratios. *J Bone Joint Surg* 82: 315-321.
13. Kummer F, Shah S, Iyer S, DiCesare P (1999) The effect of acetabular cup orientations on limiting hip rotation. *J Arthroplasty* 14: 509-513.
14. Lewinnek GE, Lewis JL, Tarr R, Compere CL, Zimmerman JR (1978) Dislocations after total hip replacement arthroplasties. *J Bone Joint Surg* 60: 217-220.
15. Wentzensen A, Zheng G, Vock B, Langlotz U, Korber J, et al. (2003) Image based cup navigation. *Int Orthop* 27: 43-46.
16. Hirakawa K, Mitsugi N, Koshino T, Saito T, Hirasawa Y, et al. (2001) Effect of acetabular cup position and orientation in cemented total hip arthroplasty. *Clin Orthop Relat Res* 388: 135-142.
17. Rittmeister M, Calllitsis C (2006) Factors Influencing Cup Orientation in 500 Consecutive Total Hip Replacements. *Clin Orthop Relat Res* 445: 192-196.
18. Charnley J (1970) Total hip replacement by low friction arthroplasty. *Clin Orthop Relat Res* 72: 7-21.
19. Coventry MB (1985) Late dislocations in patients with Charnley total hip arthroplasty. *J Bone Joint Surg* 67: 832-841.
20. Houshan Lv (1998) Artificial joint surgery. First Edition. Beijing: Science and Technology Press 9.
21. Wang YC (2001) Bone and joint injury. People's Medical Publishing House, Beijing, china.
22. Ma RF, Liu ShL, Xu J (2002) The measurement of proximal femur and its clinical significance. *Clinical J Orthopaedics* 5: 164-166.